329343D02 ROOT OBSERVATION DETAIL - CONTAINER



Notes:

1- Observations of roots shall occur prior to acceptance. Roots and substrate may be removed during the observation process; substrate/soil shall be replaced after observation has been completed.

2- Small roots (¼" or less) that grow around, up, or down the root ball periphery are considered a normal condition in container production and are acceptable however they should be eliminated at the time of planting. Roots on the periperhy can be removed at the time of planting. (See root ball shaving container detail).
3- See specifications for observation process and requirements.



ROOT OBSERVATIONS DETAIL - CONTAINER

Source: Urban Tree Foundation

329343D02 ROOT OBSERVATION DETAIL - CONTAINER Dated: 03/05/18 Applies to: All Projects University of Kentucky